Secrets. H.-57—100,000—31-8-55.

Public Works **(195 6) Departme**



Ms. **SERIES.**

G.O. No. 4398

Dated 23rd October, 56

Clos

Supd

FOR MYSORE STATE

[Despatch Abstract.]

Electricity - Pykara Electricity System - South Kanara Dt - Scheme for extension of supply of power from Kumbla to Kasaragode and enroute villages - Sanctioned.

E

1

GOVERNMENT ELECTRICITY DEPARTMENT

From
Sri V.P. Appadurai, B.A.
M.I.E., (IND).,
Chief Engineer(Electricity);
157, Mount Road, Madras-2.

To
The Secretary to Government;
Public Works Department,
Fort St. George, Madras-9.

ASST. SECRETARY TO GOVERNMENT 45 3 JAN 1956 PUBLIC WORKS DEPARTMENT

NO.ER/A3/R1/2816F/53-21 Dated 31 -12 -1955.

Sub:-Electricity-Pykara Electricity Sytem-Proposal for 11KV Extension from Kumbala 33/11 KV.S.S. to Kasargode and enroute villages-South Kanara District.

******

I forward herewith a proposal for extending supply of power from Kumbla to Kasargode and enroute villages in South Kanara District.

2 The Scheme has been prepared on ten year basis and the report enclosed gives the details of loads revenue forecast and estimates. The initial outlay works out to Rs.7.045 lakhs and the total estimate in 10 years period amounts to Rs.7.998 lakhs. The total anticipated revenue in 10 years period is Rs.832010.5 with a return of 10.4% on the total capital outlay.

3 The present scheme provides for supply of power to 3 villages of which one (viz. Mogralu) is under National Extension Service Scheme of Kumbla Firka in Manjeshwar Block of South Kanara District. The main 11 KV feeder provided in the scheme will enable individual small extensions to be made to other villages also if the scheme is completed. The expenditure is debited to 81-A Capital-outlay on Electricity Schemes-I-HES-A-Pykara HES-Development Scheme-Five year plan Scheme-(a) Works -4-~~Extra~~ costing over Rs.2 lakhs extension of supply from Kumbla to Kasargode etc. villages. Details as per P.W.D. Memo No.3373J/47-1 dated 2-9-47 are furnished in scheme report. The proposal and estimate are forwarded herewith for according administrative approval of Government.

for CHIEF ENGINEER FOR ELECTRICITY.

ms.29/12.

S C H E M E R E P O R T

Extension of Electricity

from Kumbla to Kasargode

and enroute villages

South Kanara District.

PYKARA SYSTEM

Cost Rs.7.99763 Lakhs.

5

CONTENTS.

		Page No.
1)	Topographical layout of Scheme (Plate I)	1 to 7
2)	General.	1 to 9
3)	Scheme.	1 to 9
4)	Load Forecast.	1 to 2 & 5-11
5)	Estimate.	3 to 13
6)	Revenue Forecast and financial results.	3 to 13
7)	Construction Programme.	3 — do —
8)	Details required as per P.W.D. Memo.3373J/47-1 dated 2-9-47.	4 to 15
9)	Annexure I (Summary of estimate)	5 to 17
10)	Annexure II (Detailed estimate)	6 to 10 & 15-27
11)	Annexure III (Load Forecast)	11 to 29
12)	Annexure IV (Revenue Forecast)	12 to 31
13)	Annexure V (H.T. and L.T. line Schddule)	13 to 33
14)	Annexure VI (Distribution Transformers Schedule)	14 to 35
15)	Annexure VII List of Industrial loads in first year.	15 to 37
16)	Annexure VII List of Agricultural loads in first year.	15 to 37
17)	Layout of 33/11 KV. S.S. at Kumbla	Plate II. to 41

***



REFERENCE.

- 33 KV LINE.
- 11 KV LINE WITH 7/.074 PROPOSED NOW.
- " " " " 3/.104 " "
- PROPOSED TRANSFORMER STATION UNDER PRESENT SCHEME IN 1ST YEAR.
- PROPOSED TRANSFORMER STATION UNDER PRESENT SCHEME IN 2ND TO 10TH YEAR.
- PROPOSED TRANSFORMER TO BE INCREASED IN CAPACITY 2ND TO 10TH YEAR.
- RIVER.

Plate I

EXTENSION OF 11KV LINE FROM KUMBLA 33/11KV SS. TO KASARAGODE, S KANARA DT.

SCALE: 1" = 1 MILE.

SK No: 5005

DRAWN:

TRACED:

CHECKED:

APPROVED:

DATE: 2-9-55.

Erection of 33/11 K.V. S.S. at Kumbla and 11 K.V. Extension from Kumbla to Kasargode and enroute villages in South Kanara Dist.

***

SCHEME REPORT.

1. GENERAL:

The proposal is to extend supply of electricity to Kasargode, Kudlu and Mogralu, villages of South Kanara District. The power will be utilised mainly for agricultural, street lights and domestic purposes. The source of supply will be from Jog Hydro Electric Scheme of Mysore Government.

2. SCHEME: The scheme comprises mainly of the following.

1) Erection of one 33/11 KV. S.S. at Kumbla with 2 Nos. 500 KVA. Power Transformers.

2) Erection of 10.0 miles of 11 K.V. line with 7/.104 copper and 1.5 miles of 11 KV. with 3/.104 copper.

3) Erection of 11.5 miles of L.T. line with various sizes of all aluminium conductors.

4) Erection of 8 Nos. 11 KV/400V Distribution Transformers in various villages.

5) Taking over of the Kasargode licensee for which provision of Rs.75,000/- has been made in the estimate.

6) The following additions of distribution transformers and also lines during the 10 year period are contemplated.

1) Erection of 1 No. distribution transformer and enhancement of 3 Nos. of distribution transformers.

2) Erection of 7 miles of L.T. line with various sizes of all Aluminium Conductors.

The main 33 K.V. line from Mangalore S.S. to Kumbla to feed the 33/11 KV. S.S. at Kumla from which S.S., these villages will be fed will be constructed under the funds available for "33 K.V. lines and Sub-stations" under the South Kanara Scheme already sanctioned by Government in G.O. No.Ms.441 dt. 5-2-52. The necessary working estimate for this will be sanctioned by the Chief Engineer for Electricity.

3) Load Forecast. The layout of the extension of the 33/11 K.V. S.S. at Kumbla is indicated in the enclosed sketch. The bulk of the load anticipated in the area are for.

1) Industrial (2) Agricultural (3) Domestic Services and (4) Street Lights.

The types of industrial loads expected are mainly Saw Mills, Oil Mills and flour Mills. Some of these are already in existence using oil engine drive and they are all prepared to change over to electric drive as soon as electricity is made available. There are no rice mills included. The industrial load expected is of the order of 760 H.P. in the first year itself. A list of parties of industrial load is also enclosed.

contd....

The Agricultural loads contemplated are mainly for pumping water for agricultural purposes from wells and rivers having copious supply of water in the area. The agricultural loads expected are of the order of 76 H.P. initially rising to 275 H.P. in 10 years. A list of parties of agricultural loads in the first year is also enclosed.

There is also great demand for domestic lighting, Bazaar lighting, and Panchayat Street lighting, as most of these villages are having Panchayat Board administration.

Kasargode town is already having electricity on a small scale, generated and distributed by a licensee M/s. Kanara Ceremic's Ltd. and this licensee is not able to meet the growing demand even within the town area.

The licensee's power house consists of

1. One number 75 KVA. generator

2. One number 27.5 KVA. generator

3. One number 25 KVA. 350/440V booster.

Number of services -- 332

Length of L.T. line -- 7 miles

Provision is made in this scheme for taking over of this licensee by Government so that the supply position may be improved and the growing demand of the public here is fully met.

Load Forecast

	1st year	10th year.
Industrial.	760 H.P.	760 H.P.
Agricultural.	76 H.P.	275 H.P.
Domestic.	645 Nos.	880 Nos.
Street Lights.	270 Nos.	270 Nos.
F.R.S.C. (shop)	120 Nos.	210 Nos.
Cinema.	2	2

Annexure III gives the detailed load forecast in respect of the various loads for the 10 year period.

One of the villages viz. Mogralu is under National Extension Service Scheme of Kumbla Firka in Manjeshwar Block of South Kanara District.

This scheme will benefit a total population of 31259 residing in 3 villages in all. It will provide electricity for 11 Nos. Industrial loads and irrigation for 250 acres, illuminate 880 houses and provide electricity for 270 street lights.

contd.....

4. ESTIMATE:

The scheme is estimated to cost Rs.7.0452 lakhs initially rising to Rs.7.99763 lakhs in the 10th year. Annexure I and II give the abstract and detailed estimate respectively, The estimates are worked out with currant prices of construction materials.

5. REVENUE FORECAST AND FINANCIAL RESULTS:

Annexure IV gives the revenue forecast for the 10 year period.

	Rs.
1st Year	68005
2nd year	73931.25
3rd year.	79717.5
4th year	85503.75
5th year	87475.5
6th year	87475.5
7th year	87475.5
8th year	87475.5
9th year	87475.5
10th year.	87475.5
Total for 10 year	Rs. 832010.5

The financial results are as follows:

Total cost of extensions for the 10 year period.	Rs. 799763
Total revenue for 10 year period.	Rs. 832010.5
Average return/year.	Rs. 83201.05

$$\% \text{ return} = \frac{83201.05}{799763} \times 100 = \underline{10.4\%}$$

The scheme is therefore remunerative.

6. Construction Programme:

The initial scheme is expected to be completed in one year after receipt of sanction by which time the Jog supply to South Kanara District would have materialised.

7. Details required as per P.W.D. Memo No.3373J/47-1 dated 2-9-47 are furnished below:

contd....

15

-4-

INFORMATION TO BE FURNISHED ALONG WITH THE PROPOSALS FOR NEW SCHEMES FOR INTRODUCTION IN THE CURRENT YEAR WITH REFERENCE TO GOVERNMENT MEMO.NO.3373-J/47-1 DATED 2ND SEPTEMBER, 1947.

***

1.	Major head of Account.	81.A. Capital outlay on Elecy. Schemes-I H.E.S. - A. Pykara H.E.S. - Development Scheme & Five Year Plan Scheme -(a)Works 4. Exth. costing over Rs.2 lakhs Extension of supply from Kumbla to Kasargode etc. villagges.
2.	Minor and Subhead of Account.	
3.	Ultimate cost - Recurring. Non-Recurring.	Rs.92,000 Rs.7,99,800
4.	Cost in the year of introduction. Recurring & Non-Recurring.	Nil Rs.1,76,200
	(The estimate of cost in the year of introduction should be based on the best estimate possible of the probable date of introduction and other relevant factors.)	
5.	The total budget allotment under the major head of account.	Rs.11.40 Crores (R.E.1955-56)
6.	The actual expenditure under the same major head in the current year to the end of the latest month for which the figures are available.	Rs.397.16 lakhs (To end of November 1955)
7.	The source from which or the method by which it is proposed to meet the expenditure on the scheme in the current year if it is sanctioned(e.g.) from a lump sum allotment provided for in the budget, or by curtailing expenditure on the sanctioned schemes and	By applying Supplementary Grant for 1955-56.
8.	The savings, recurring or non-recurring anticipated under the above items of expenditure under the major head and the reasons for such anticipation.	No savings are anticipated.

For CE (Electrical)

ANNEXURE - I

SUMMARY OF ESTIMATE FOR EXTENSION OF SUPPLY FROM KUMBLA 33/11 KV. S.S. TO KASARGODE AND ENROUTE VILLAGES.

	Amount Rs.	Total Rs.
A) 33/11 K.V. S.S. at Kumbla I year.	251160	
B) 11 K.V. Main lines and distribution 1st year.	378360	704520
Compensation to Kasargode Licensee 1st year.	75000	
C) 11 K.V. lines and distribution in second to 10th year.	95243	95243
Total for 10 years. Rs.		799763

REVENUE FORECAST

Total anticipated revenue in 10 years. = Rs.832010.5

Total anticipated revenue in one year. Rs. 83201.05

Total capital outlay in 10 years. Rs.799763

Therefore % return = $\frac{83201.05}{799763} \times 10 = 10.4\%$

***

15

ANNEXURE - II

A) 33/11 K.V.S.S. at Kumbla, (1st year).

Qty.	Description.	Rate	Per	Amount	Total
	I. Grounds and Buildings.				
	Site Buildings etc.	50,000	L.S.	50,000	50,000
	II. Foundation and Structures:				
2 Nos.	33 K.V.Bus structures erected complete with insulators, busbars etc.	7,500	Each	15,000	
2 Nos.	33 KV. H.G. Fuse Structures.	1,000	each	2,000	
2 Nos.	11 KV.Bus structures erected complete with insulators busbars etc.	6,000	each	12,000	
2 Nos.	11 KV. feeder take off structures.	500	each	1,000	
1 No.	11 KV. Station Transformer Fuse structures.	500	each	500	30,500
	H.T. Switchgear erected:				
3 Nos.	33 KV. AB. Switches erected.	4,000	each	12,000	
2 sets.	33 KV. H.G. Fuses.	1,500	set	3,000	15,000
	Transformers erected.				
2 Nos.	500 KVA 33/11 KV Transformers erected.	23,000	each	46,000	
1 No.	25 KVA 11KV/400V Transformers erected.	4,000	each	4,000	
	Plinths for above L.S.	1,500	each	3,000	53,000
	Lightning Arresters erected:				
1 set	33 KV. Lightning Arresters(Station) (Station type)	6,500	set	6,500	
2 sets	11 KV. -do- -do-	2,000	set	4,000	
1 set	11 K.V. Lightning Arresters (Distribution Type)	350	set	350	10,850
	Switchgear & Instruments:				
1 No.	Transformer Alarm Panel.	2,000	each	2,000	
1 No.	O.C.B. Alarm Panel.	2,000	each	2,000	
1 No.	30V Battery.	2,000	each	2,000	
1 No.	Recording Voltmeter to work off 11 KV/110V P.T.	750	each	750	6,750
	L.T. Switchgear:				
8 Nos.	11 KV. A.B. Switches.	1,500	each	12,000	
2 Nos.	Frame mounted O.C.B.	12,000	each	24,000	
1 set	11 KV. H.G. Fuse.	500	each	500	
	Control Cable L.F.	2,500	each	2,500	
	Earth connections L.S.	2,000	each	2,000	41,000
					2,07,100
	Contingencies 5%				10,355
					2,17,455
	Establishment and General Charges 15%				32,618
	T & P for construction 3%				6,524
	T & P for O & M 1/2%				1,087
					2,57,684
	Less credits for construction T&P				6,524
				Rs.	2,51,160

(B) DETAILED ESTIMATE OF KUMBLA - KASARGODE 11 KV. EXTENSION 1ST YEAR.

Qty.	Description.	Rate Rs.	Per	Amount Rs.	Total. Rs.
	I. GROUNDS AND BUILDINGS.				
11.5M	Tree clearance cutting compensation etc.	300	Mile	3,450	3,450
	II. H.T. FEEDERS ERECTED.				
10 M	11 KV. H.T. line with 7/.074 Cu. on rail poles 300' Span.	8,900	Mile	89,000	
1.5 M	-do- with 3/.104 Cu.	8,000	Mile	12,000	1,01,000
	III. SPECIAL STRUCTURES ERECTED:				
8 Nos.	Transformer structure 10' centre.	900	Each	7,200	7,200
	IV. H.T. SWITCHGEAR ERECTED:				
8 Nos.	11 KV. AB. Switches.	370	Each	2,960	
8 Nos.	11 KV. HG. Fuses.	113	Each	904	
5 Nos.	11 KV. L.A. Fuses.	270	Each	1,350	
	Labour and Transport.	100	Each	800	
	Sundries.			86	6,100
	V. TRANSFORMERS ERECTED.				
3 Nos.	25 KVA. 11 KV/400V Transformer.	3,300	Each	9,900	
3 Nos.	50 KVA. -do-	3,900	Each	11,700	
2 Nos.	100 KVA. -do-	5,300	Each	10,600	
	Labour and Transport.	250	Each	2,000	
	Sundries.		L.S.	150	34,350
	VI. L.T. FEEDERS ERECTED.				
1.5 M	L.T. 3 phase 5 with 7/.0975 plus 7/.0772 Aluminium conductor on wood poles 150' span.	6,690	Mile	10,035	
2.5'M	L.T. single phase 3 wire with 7/.0772 Al. on wood poles 150' span.	4,640	Mile	11,600	
2.5 M	-do- 2 wire.	3,740	Mile	9,350	

dontd..

Quantity.	Description.	Rate	Per	Amount	Total.
		Rs.		Rs.	Rs.
4 M	L.T.3ph. 4 wire with 7/.0772 with all aluminium with wood poles 250' span.	3,750	Mile	15,000	
1 M	-do- with 7/.0975 and 7/.0772.	4,550	Mile	4,550	50,535
	VII. L.T. SWITCHES ERECTED.				
8 Nos.	L.T. Distribution Box.	400	Each	3,200	
8 Nos.	L.T. Lightning Arresters.	50	Each	400	
	Labour and Transport.		L.S.	450	
	Sundries.			100	4,150
	VIII. STREET LIGHT FIXTURES ERECTED.				
270 Nos.	St. Light fixtures.	60	Each	16,200	
4 Nos.	Switches.	50	Each	200	16,400
	IX. SERVICES ERECTED.				
9 Nos.	Agricultural Services.	250	Each	2,250	
645Nos.	Domestic services.	110	Each	70,950	
120Nos.	F.R.S.Cs.	85	Each	10,200	
12 Nos.	Industrial services.	400	Each	4,800	
2 Nos.	Cinema.	300	Each	600	88,800
	Sub-total.				3,11,985
	Contingencies 5%				15,599
	Total for works.				3,27,584
	Establishment and General charges			15%	49,138
	Construction T & P			3%	9,827
	T & P for O & M			1/2%	1,638
					3,88,187
	Less credits for T & P				9,827
					3,78,360
	Cost towards taking over of Kasargode licensee		L.S.		75,000
	Total.				4,53,360

(C) 2ND TO 10TH YEAR.

Quantity.	Description.	Rate	Per	Amount	Total.
		Rs.		Rs.	Rs.
	I. GROUNDS & BUILDINGS.				
	Nil			Nil	Nil
	II. H.T. FEEDERS ERECTED.				
	Nil.				
	III. SPECIAL STRUCTURES ERECTED.				
1 No.	10' Centre transformer structure.	900	Each	900	900
	IV. H.T. S.G. ERECTED.				
1 No.	A.B. Switch 11 KV.	370	Each	370	
1 No.	H.G. Fuse 11 KV.	113	Each	113	
3 Nos.	11 KV. L.As.	270	Each	810	
	Labour and Transport.		L.S.	100	
	Sundries.		L.S.	17	1,410
	V. TRANSFORMERS ERECTED:				
1 No.	25 KVA. 11 KV/400V.	3,300	Each	3,300	
	Increase of transformer capacity.				
2 Nos.	25 KVA. to 50 KVA. 11 KV/ 400V.	800	Each	1,600	
1 No.	25 KVA. to 75 KVA. 11 KV/ 400V.	1,500	Each	1,500	
	Labour and Transport.		LS	1,500	
	Sundries.		LS	150	8,050
	VI. L.T. FEEDERS ERECTED.				
2.5 M	L.T. single phase 2 wire line with 7/.0772 all aluminium on wood poles 150' span.	3,740	Mile	9,350	
0.5 M	L.T. 3 phase 4 wire with 7/.0975 and 7/.0772 all aluminium on wood poles 250' span.	4,550	Mile	2,275	
4 M	L.T. 3 phase 4wire with 7/.0772 all aluminium on wood poles 250' span.	3,750	Mile	15,000	26,625

contd...

Quantity.	Description.	Rate Rs.	Per	Amount Rs.	Total Rs.
	VII. L.T. S.G. ERECTED.				
1 No.	L.T. Distribution Box.	400	Each	400	
1 No.	L.T. Lightning Arresters.	50	Each	50	
	Labour and Transport.		LS	75	
	Sundries.		LS	25	550
	VIII. St. LIGHT FIXTURES ERECTED.			Nil	
	IX. SERVICES ERECTED.				
30 Nos.	Agricultural.	250	Each	7,500	
235 "	Domestic.	110	Each	25,850	
90 Nos.	F.R.S.C.	85	Each	7,650	41,000
			Sub-total.		78,535
			Contingencies 5%		3,927
					82,462
			Establishment and General charges - 15% .		12,369
					94,831
			Tools and Plant for construction 3%		2,474
			Tools and Plant for Operation and Maintenance - 1/2%		412
					97,717
			Less credits for Tools and Plant		2,474
					95,243

LOAD FORECAST ANNEXURE III.

KUMBLA-KASARGODE EXTENSION.

No. Stations.	1st Yr.	2nd Yr.	3rd Yr.	4th Yr.	5th Yr.	6th Yr.	7th Yr.	8th Yr.	9th Yr.	10th Yr.
I. AGRICULTURAL H.P.										
1. Mogralu.	31	45	60	75	75	75	75	75	75	75
2. Kundlu.	40	60	90	120	120	120	120	120	120	120
3. Kasargode.	5	35	50	65	80	80	80	80	80	80
II. DOMESTIC.										
1. Mogralu.	20	40	60	80	80	80	80	80	80	80
2. Kundlu.	25	50	75	100	100	100	100	100	100	100
3. Kasargode.	600	625	650	675	700	700	700	700	700	700
III. STREET LIGHTS.										
1. Mogralu.	-	-	-	-	-	-	-	-	-	-
2. Kundlu	30	30	30	30	30	30	30	30	30	30
3. Kasargode.	240	240	240	240	240	240	240	240	240	240
IV. F.R.SC.										
1. Mogralu.	10	20	30	40	40	40	40	40	40	40
2. Kundlu.	10	15	20	25	30	30	30	30	30	30
3. Kasargode.	100	110	120	130	140	140	140	140	140	140
V. CINEMA.										
1. Mogralu.	-	-	-	-	-	-	-	-	-	-
2. Kundlu.	1	1	1	1	1	1	1	1	1	1
3. Kasargode.	1	1	1	1	1	1	1	1	1	1
VI. INDUSTRIAL H.P.										
1. Mogralu.	-	-	-	-	-	-	-	-	-	-
2. Kundlu	50	50	50	50	50	50	50	50	50	50
3. Kasargode.	710	710	710	710	710	710	710	710	710	710

ANNEXURE - IV.

KUMBLA - KASARGODE EXTENSION.
REVENUE FORECAST

	1st year	2nd year	3rd year	4th year	5th year	6th year	7th year	8th year	9th year	10th year	Total
Agricultural Rs.35/- per HP	76 HP 2660	140 HP 4900	200 HP 7000	260 HP 9100	275 HP 9625	275 HP 9625	275 HP 9625	275 Hp 9625	275 HP 9625	275 HP 9625	81,410
Domestic at Rs.45/-. service	645 29025	715 32175	785 35325	855 38475	880 39600	880 39600	880 39600	880 39600	880 39600	880 39600	3,72,600
Street lights (Rs.18 + 10%) Rs.19/8/- for street lights	270 5346	270 5346	270 5346	270 5346	270 5346	270 5346	270 5346	270 5346	270 5346	270 5346	53,460
F.R.S.C. (Rs.19.5 + 10%) Rs.21.45/- for service	120 2574	145 3110.25	170 3646.5	195 4182.75	210 4504.5	210 4504.5	210 4504.5	211 4504.5	210 4504.5	210 4504.5	40540.5
Cinema Rs.1200/- permanent Rs.600/- (Tent)	1 + 1 1800	1 + 1 1800	1 + 1 1800	1 + 1 1800	1 + 1 1800	1 + 1 1800	1 + 1 1800	1 + 1 1800	1 + 1 1800	1 + 1 1800	18,000
Industrial at Rs.35/- per H.P	760 HP 26600	760 HP 26600	760 HP 26600	760 HP 26600	760 HP 26600	760 HP 26600	760 HP 26600	760 HP 26600	760 HP 26600	760 HP 26600	2,66,000
Total	68005	73931.25	79717.5	85503.75	87475.5	87475.5	87475.5	87475.5	87475.5	87475.5	832010.5

33

ANNEXURE V

11 KV SUPPLY FROM KUMBLA TO MOGRALU, DUDLU

AND KASARGODE

SCHEDULE OF H.T. & L.T. LINES.

	H.T. 11 KV line		3 ph 5w	S.ph 3W	S.ph 2w	3ph 4w	3 ph 4w	Total
	7/.074 Cu	3/.104 Cu	with 7/.0975 All Al. plus 7/.0772	with 7/ .0772 Al.	with 7/ .0772 Al	with 7/.0975 Al. plus 7/.0772	with 7/ .0772	
1st Year								
1. Mogralu	2				1		1	2
2. Kudlu	4.5	1	0.5	1.5	0.5		1.5	4
3. Kasargode	3.5	0.5	1	1	1	1	1.5	5.5
Total	10.0	1.5	1.5	2.5	2.5	1	4.0	11.5
2nd to 10th year								
1. Mogralu					1		1	2
2. Kudlu					0.5		1.5	2
3. Kasargode					1	0.5	1.5	3
Total	Nil	Nil	Nil	Nil	2.5	0.5	4.0	7

ANNEXURE VI

KUMBLA KASARGODE EXTENSION

DISTRIBUTION TRANSFORMER

		1st year	2nd to 10th year
1.	Mogralu	1 No. 25 KVA	Increased from 25 KVA to 75 KVA
2.	Kudlu	2 Nos. 25 KVA 1 No. 50 KVA	2 Nos. 25 KVA increased to 50 KVA
3.	Kasargode	2 Nos. 50 KVA 2 Nos.100 KVA	1 No. 25 KVA

***

LIST OF AGRICULTURAL CONSUMERS.

FIRST YEAR

MOGRAL VILLAGES

Sl.No.	Name of Party.	Load applied.	S.F. No.	Nature of load.
1.	M.A. Mahammed P.O.Mogral	5 H.P.	-	Agricultural
2.	M. Mohammed Malabr ""	6 H.P.	-	"
3.	M.S. Mogral. ""	10 H.P.	-	"
4.	M. Abdul Khader S/o Kunchimatinkutty. ""	10 H.P.	-	"
	Total	31 H.P.		

Total applied load for agricultural pumpsets 31 H.P.

KUDULU VILLAGE

1.	K. Eswara Shanbhog President of Kudulu P.O. Kudulu Panchayat.	10 H.P.	-	Agricultural
2.	-do-	20 H.P.	-	"
3.	-do-	5 H.P.	-	"
4.	K. Appaya Naick S/o Ramya Nayakulu.	5 H.P.	-	"
	Total	40 H.P.		

Total 40 H.P. Agricultural.

KASARGODE.

1.	Sri Krishna Rao, Manager, Sri Ganesh Mill, Madur Village.	5 H.P.	Agricultural.

contd...

INDUSTRIAL CONSUMERS

First Year

KASARGODE.

1. Sri Krishna Rao, Manager of Sri Ganesh Mill.	Madur village	50 H.P.	Saw Mill existing.
2. Sri K.K.S. Kamath, Prakasha Oil Mill.	Adkathabailu	30 H.P.	Oil Mill existing.
3. -do-	Kasba.	10 H.P.	Flour Mill proposed.
4. Forest Farm Ltd.	Madur.	100 H.P.	Saw Mill existing.
5. Sri M.G. Nayak.	Kasargode.	10 H.P.	Oil Mill proposed.
6. M. Kunchambu.	Kasba.	80 H.P.	Saw Mill existing.
7. Sri Lakshimi Saw Mills Limited.	Kasargode.	150 H.P.	-do-
8. K.A. Bhat.	"	20 H.P.	Oil Mill proposed.
9. Veerasimha Nayak Sri Gopalakrishna General Trades.	"	120 H.P.	Saw Mill.
10. C. Abdul & Co.	"	20 H.P.	Saw Mill existing but hand operated.
11. Kasargode Timber Works.	""	120 H.P.	Saw Mill existing.
		710 H.P.	

Total load 710 H.P. for industries.

KUDULU:

1. Sri K. Eshwar Shambog President of Panchayat Board.		50 H.P.	Proposed oil mill.
	Total	50 H.P.	



REFERENCE

- TRANSFORMER.
- POTENTIAL TRANSFORMER.
- OIL CIRCUIT BREAKER.
- ISOLATING SWITCH WITH ARCING HORN.
- FUSE.
- LIGHTNING ARRESTER.

LAY OUT OF 33/11KV. S.S. AT KUMBLA.

Plate II

SK.No. 1.

DRAWN:

TRACED:

CHECKED:

APPROVED:

DATE.

PUBLIC WORKS DEPARTMENT.

43

NOTE FOR THE STANDING FINANCE COMMITTEE.

SUB: Electricity - Pykara Electricity System - South Kanara District - Extension of supply of power from Kumbla to Kasargode.

****

SUMMARY OF COST.

Major Head of account	Minor and sub-head of account.	Ultimate cost		Cost in the year of introduction.
		Recurring	Non-recurring	Non-recurring.
31.A. Capital Outlay on Electficity Schemes.	Development Schemes - Five Year Plan Schemes - I.Hydro Electric Scheme - A.Pykara Hydro Electric Scheme - a. works - 4.Extensions coming over Rs.2 lakhs Extension of supply from Kumbla to Kasargode villages.	Rs. 92,000/-	Rs. 7,99,800/-	Rs. 100/-

This proposal is for extension of supply of power for agricultural, industrial, domestic and street lighting purposes from Kumbla to Kasargode and en-route villages in South Kanara District.

2. The scheme has been prepared on a ten year basis. The initial outlay works out to Rs.7,045 lakhs and the total estimate in 10 years period comes to Rs.7.998 lakhs. The total anticipated revenue in 10 years period is Rs.8,32,010.5 and it works out to 10.4% on the capital outlay. As the return exceeds the standard return of 10%, the scheme is remunerative.

3. The scheme envisages supply of

electricity to Kasargode, Kudlu and Mogralu villages.

The load forecasts in the 1st and 10th year are as follows:-

Load forecast	1st year	10th year
Industrial	760 H.P.	760 H.P.
Agricultural	76 H.P.	275 H.P.
Domestic	645 Nos.	880 Nos.
Street lights	270 Nos.	270 Nos.
F.R.S.C.(Shops)	120 Nos.	210 Nos.
Cinemas	2	2

The types of industrial loads expected are mainly Saw Mills, Oil Mills and Flour Mills. There are no rice mills included in the scheme. The agricultural loads contemplated are mainly for pumping water for agricultural purposes from wells and rivers having copious supply of water in the area.

4. Mogralu village included in the Scheme is under the National Extension Service Scheme of Kumbla firka in Manjeswar Block of South Kanara District. The main 11 K.V. feeder provided in the scheme will enable individual small extensions to be made to other villages also if the scheme is completed. The source of supply will be from Jog Hydro Electric Scheme and the initial scheme is expected to be completed in one year after the scheme is sanctioned by the Govt. by which time the Jog supply to South Kanara District, would have materialised.

5. Kasargode town, which has been included in the scheme, is already having electricity on a small scale, generated and distributed by a licensee M/s. Kanara Ceramic's Ltd., and the licensee is not able to meet the growing demand even within

the town areas. It is therefore proposed to take over the undertaking by the Govt. so that supply position may be improved and the growing demand of the public in the town fully met. A provision of Rs.75,000/- towards compensation to the licensee in the first year has been provided in the estimate.

6. In view of the States Re-Organisation proposals, provision has not been included in the Part II Scheme proposals for 1956-57 for the acquisition of the Kasargode undertaking. Therefore the question has to be considered whether the present proposal which includes agquisition of the above undertaking, may be proceeded with. There has been considerable agitation in South Kanara Dist. against the postponement of the acquisition of the Mangalore Elecy. undertaking. To sanction the scheme following the usual financial procedure will take some time and by that time the final decision regarding the States Re-Organisation proposal is likely to be known. The C.E. has also reported separately that the acquisition of the undertaking is programmed only for March 57. If Kasargode is to go to another State, the acquisition will have to be done only by that State. In the circumstances this Deptt. proposed that the scheme may be sanctioned. Fin deptt have agreed *

7. The estimated cost of the scheme exceeds Rs.2 lakhs. The scheme has therefore to be treated as 'new service' and placed before the S.F.C. and the Cabinet. The approval of Legislature has also to be obtained in due course.

8. With the approval of the M(W) & M(F & E), the proposal is placed before the S.F.C. for consideration.

9/5/56
11/5/56
11/5/56

PUBLIC WORKS DEPARTMENT. 42

NOTE FOR THE STANDING FINANCE COMMITTEE.

SUB: ELECTRICITY - Pykara Electricity System - South Kanara District - Extension of supply of power from Kumbla to Kasaragod.

...

SUMMARY OF COST.

Major Head of account	Minor and sub-head of account	Ultimate cost		Cost in the year of introduction
		Recurring	Non-recurring	Non-recurring.
		Rs.	Rs.	Rs.
81. A.Capital Outlay on Electricity Schemes.	Development Schemes-Five Year Plan Schemes - I.Hydro Electric Scheme-A. Pykara Hydro Electric Scheme - a. works -4.Extensions coming over Rs.2 lakhs - Extension of supply from Kumbla to Kasargode villages.	92,000/-	7,99,800/-	100/-

The proposal is for extension of supply of power for agricultural, industrial, domestic and street lighting purposes from Kumbla to Kasargode and en-route villages in South Kanara District.

2. The scheme has been prepared on a ten year basis. The initial outlay works out to Rs.7.045 lakhs and the total estimate in 10 years period comes to Rs.7.998 lakhs. The total anticipated revenue in 10 years period is Rs.8,32,010.5 and it works out to 10.4% on the capital outlay. As the return exceeds the standard return of 10%, the scheme is remunerative.

3. The scheme envisages supply of electricity to Kasargode, Kudlu and Mogralu villages. The load forecasts in the 1st and 10th years are as follows:-

Load forecast	1st Year	10th Year
Industrial	760 H.P.	760 H.P.

p.t.o.

(1)	(2)	(3)
Agricultural	76 H.P.	275 H.P.
Domestic	645 Nos.	880 Nos.
Street lights	270 Nos.	270 Nos.
F.R.S.C.(Shops)	120 Nos.	240 Nos.
Cinemas	2	2

The types of industrial loads expected are mainly Saw Mills, Oil Mills and Flour Mills. There are no rice mills included in the scheme. The agricultural loads contemplated are mainly for pumping water for agricultural purposes from wells and rivers having copious supply of water in the area.

4. Mogralu village included in the Scheme is under the National Extension Service Scheme of Kumbla firka in Manjeswar Block of South Kanara District. The main 11 K.V.feeder provided in the scheme will enable individual small extensions to be made to other villages also if the scheme is completed. The source of supply will be from Jog Hydro Electric Scheme and the initial scheme is expected to be completed in one year after the scheme is sanctioned by the Government by which time Jog supply to South Kanara District would have materialised.

5. Kasaragode town, which has been included in the scheme, is already having electricity on a small scale, generated and distributed by a licensee M/s.Kanara Ceremic's Ltd., and the licensee is not able to meet the growing demand even within the ~~twen~~ town areas. It is therefore proposed to take over the undertaking by the Government so that supply position may be improved and the growing demand of the public in the town fully met. A provision of Rs.75,000/- towards compensation to the licensee in the first year has been provided in the estimate.

6. In view of the States- Re-Organisation proposals, provision has not been included in the Part II Scheme proposals for 1956-57 for the acquisition of the Kasargode undertaking. Therefore the question has to be

p.t.o.

considered whether the present proposal which includes acquisition of the above undertaking, may be proceeded with. There has been considerable agitation in South Kanara District against the postponement of the acquisition of the Mangalore Electricity undertaking. To sanction the scheme following the usual financial procedure will take some time and by that time the final decision regarding the States Re-organisation proposal is likely to be known. The Chief Engineer has also reported separately that the acquisition of the undertaking is programmed only for March 56 1957. If Kasargode is to go to another State, the acquisition will have to be done only by that State. In the circumstances this department proposed that the scheme may be sanctioned. Finance Department have agreed.

7. The estimated cost of the scheme exceeds Rs.2 lakhs. The scheme has therefore to be treated as 'new service' and placed before the S.F.C. and the Cabinet. The approval of Legislature has also to be obtained in due course.

8. With the approval of the M(W) & M(F & E), the proposal is placed before the S.F.C. for consideration.

R.M. SUNDARAM
SECRETARY TO GOVERNMENT.
18.5.1956.

ml.25.5.

GOVERNMENT ELECTRICITY DEPARTMENT.

51



From

Sri V.R. Appadurai, B.A., M.I.E.(Ind).,
Chief Engineer for Electricity,
157, Mount Road, Madras-2.

To

The Secretary to Government,
Public Works Department,
Madras-9.

No. 2816-F/53-22, dated 15-9-1956.

Sir,

Sub: Electricity - Pykara Electricity System - Proposal for 11 KV. extension from Kumbla 33/11 KV. sub-station to Kasaragode and enroute villages.-South Kanara District - Sanction requested.

Ref: My letter No. ER/A3/R1/2816/53-21, dt. 31-12-1955.

I request early orders of Government sanctioning the proposal forwarded with my letter cited.

PYJ/18-9.

For Chief Engineer for Electricity

C.No.45-E/56
ORIGINAL TO MYSORE STATE)

P.W.D.(

G.O.Ms.No. 4398 dt. 23.X

Electricity - Pykara Electricit
System - South Kanara District - Sch
for extension of supply of power fro
Kumbla to Kasargode and enroute vill
Sanctioned.

Read:-From the C.E(E) letter No.
ER/A3/R1/2816-F/53-21
dated 31-12-55.

ORDER:-

The Government sanction the
scheme for extension of supply of electri
city for agricultural, industrial, domestic and street
lighting purposes from Kumbla to Kasargode
enroute villages in South Kanara Dist.
Electricity System and sanction for
Rs. an initial expenditure of
four lakhs (Rupees seven lakhs and
rising and five hundred only)
lakhs, n 98 lakhs (Rupees seven
hundred on thousand and eight

2. to "81.4. Canal of ten years.
Schemes - Develope is debitable-
Plan Scheme - I. Electricity
Pykara Hydro Electri Five Year
Extension costing over heme-A.
sion of supply from Kumb ks -4
etc. villages, South Kanar
Pending provision of funds
head, the expenditure on the s
1956-57 which is on 'New Service
initially met by an advance from
Contingency fund and orders in this
which
will be issued from the Finance Depart

Orders regarding provision of funds will be issued separately.

parately. The C.E(E) is ~~accordingly~~ urgently requested the Government in the Finance Department an estimate of expenditure to be incurred during ~~the current year~~ 1956-57.

3. The scheme sanctioned in para.1 above is subject to the following conditions:-

(a) Supply to power load is liable to be suitably restricted, staggered or cut off altogether if the power position or any other emergency warrants such a course of action; and

(b) Supply will be cut off if it is utilised for purposes other than that for which it has been specifically sanctioned.

4.10.56
5.10.56.

10/10/56

12.10.56

To the C.E(E).
To the C.C.E(S).
To the A.G. through Finance.
To the A.G. (by name).
Copy to P.Section.(2 copies)
Kerala State.
S.Cs.2

C.No.45-E/56
ORIGINAL TO MYSORE STATE)

P.W.D.(E-2)

G.O.Ms.No. 4398 dt. 23.X.56

Electricity - Pykara Electricity System - South Kanara District - Scheme for extension of supply of power from Kumbla to Kasargode and enroute villages Sanctioned.

Read:-From the C.E(E) letter No. ER/A3/R1/2816-F/53-21 dated 31-12-55.

O R D E R:-

The Government sanction the scheme for extension of supply of electricity for agricultural, industrial, domestic and street lighting purposes from Kumbla to Kasargode and enroute villages in South Kanara Dist Pykara Electricity System and sanction for the purpose an initial expenditure of Rs.7.045 lakhs (Rupees seven lakhs and four thousand and five hundred only) rising to Rs.7.998 lakhs (Rupees seven lakhs, ninety nine thousand and eight hundred only) at the end of ten years.

2. The expenditure is debitable to "31.A. Capital outlay on Electricity Schemes - Development Scheme - Five Year Plan Scheme - I. Hydro Electric Scheme-A. Pykara Hydro Electric Scheme -(a) Works - Extension costing over Rs.2 lakhs - Extension of supply from Kumbla to Kasargode etc. villages (South Kanara District."

Pending provision of funds under ~~this~~ the head in advance with the approval of the legislature the expenditure on the scheme during 1956-57 which is on 'New Service' will be initially met by an advance from the Contingency fund ~~and~~ orders in ~~this~~ regard which will be issued from the Finance Department

Orders regarding provision of funds will be issued separately.

p.t.o

separately. The C.E(E) is ~~accordingly~~ requested to submit urgently to the Government in the Finance Department an estimate of expenditure to be incurred during ~~the current year.~~ 1956-57.

3. The scheme sanctioned in para.1 above is subject to the following conditions:-

(a) Supply to power load is liable to be suitably restricted, staggered or cut off altogether if the power position or any other emergency warrants such a course of action; and

(b) Supply will be cut off if it is utilised for purposes other than that for which it has been specifically sanctioned.

4.10.56
5.10.56.

10/10/56

12.10.56

To the C.E(E).
To the C.C.E(S).
To the A.G. through Finance.
To the A.G. (by name).
Copy to P.Section.(2 copies)
" " Kerala State.
S.Cs.2 " Govt of Mysore

P.W.D.(E-2).

Sub: Electricity - Pykara Electricity System - South Kanara Dt. - Extension of supply of power from Kumbla to Kasargode.

Ref: From the C.E.(E) lr.No.ER/A3/R1/2816 F/53-21 dt.31.12.55.

..

The Chief Engineer (Electricity) has submitted a scheme for extension of supply of power from Kumbla to Kasargode and enroute villages in South Kanara Dt.

2. The scheme has been prepared on a ten year basis. The initial outlay works out to Rs.7.045 lakhs and the total estimate in 10 years period comes to Rs.7.998 lakhs. The total anticipated revenue in 10 years period is Rs.8,32,010.5 and it works out to 10.4% on the capital outlay. As the return expected exceeds the standard return of 10%, the scheme is remunerative.

3. The scheme envisages supply of electricit to Kasargode, Kudlu and Mogralu villages for agricultural, industrial, street lighting and domestic purposes. Kasargode town is already having electricity on a small scale, generated and distributed by a licensee M/S.Kanara Ceremic's Ltd. and the licensee is not able to meet the growing demand even within the town area. It is therefore proposed to take over the undertaking by the Govt. so that supply position may be improved and the growing demand of the public in the town is fully met. A provision of Rs.75,000/- towards compensation to the licensee in the first year has been provided in the estimate.

The load forecasts in the 1st and 10th year is as follows:-

Load forecast	1st year	10th year
Industrial	760 H.P.	760 H.P
Agricultural	76 H.P.	275 H.P

Load forecast	1st year	10th year.
Domestic	645 Nos.	880 Nos.
Street lights	270 Nos.	270 Nos.
F.R.S.C.(Shops)	120 Nos.	210 Nos.
Cinemas	2	2

The types of industrial loads expected are mainly Saw Mills, Oil Mills and Flour Mills. Some of these are already in existence using oil engine drive and they are all prepared to change over to electric drive as soon as electricity is made available. There are no rice mills included in the scheme. The agricultural loads conterplated are mainly for pumping water for agricultural purposes from wells and rivers having copious supply of water in the area. Supply of power for street lighting purposes at Kundlu and Kasargode is proposed in the scheme.

4. Out of the three villages included in the scheme, Mogralu is under the National Extension Service Scheme of Kumbla firka in Manjeswar Block of South Kanara Dt. The main 11 K.V. feeder provided in the scheme will enable individual small extensions to be made to other villages also if the scheme is completed. The source of supply will be from Jog Hydro-electric Scheme and the initial scheme is expected to be completed in one year after the scheme is sanctioned by the Govt. by which time the Jog supply to South Kanara Dt. would have materialised.

5. The proposal includes provision for acquisition of the Kasargode undertaking. In view of the States Re-organisation proposals, ~~it is not proposed to take over the Kasargode undertaking during 1956-57.~~ provision has not been included in the Part II Scheme proposals for 1956-57 for the acquisition of the Kasargode undertaking. Therefore it has to be considered whether

the present proposal which includes acquisition of the above undertaking may be proceeded with. It may however be mentioned that there has been great agitation in South Kanara about the postponement of the acquisition of the Mangalore undertaking and allegations were also made that the Govt. have dropped extension schemes in the dt. in view of the S.R.C. Report. The allegations are no doubt baseless.

6. The estimated cost of the scheme exceeds Rs.2 lakhs. The scheme has thereforet to be treated as 'new service' and placed before the S.F.C. and the Cabinet. The approval of Legislature has also to be obtained in due course. To sanction the scheme following the above procedure will take some time and by that time the final decision regarding the States Re-organisation is likely to be known. The C.E. had also reported separately that the acquisition of Kasargode undertaking is programmed only for March 1957. If Kasargode is to go to another State, the acquisition will have to be done only by that State. In the circumstances the scheme may be sanctioned after obtaining the approval of the S.F.C. and the Cabinet.

7. Finance may see prior to circulation.

Finance (EB)
The proposal of P.W. at A. above may be agreed to.

P.W.

P.W.D.(E 2)

NOTE FOR CIRCULATION.

The Chief Engineer (Electricity) has submitted a scheme for extension of supply of power for agricultural, industrial, domestic and street lighting purposes from Kumbla to Kasaragode and en-route villages in South Kanara District.

2.The scheme has been prepared on a ten year basis. The initial outlay works out to Rs.7.045 lakhs and the total estimate in 10 years period comes to Rs.7.998 lakhs. The total anticipated revenue in 10 years period is Rs.8,32,010.5 and it works out to 10.4% on the capital outlay. As the return exceeds the standard return of 10%, the scheme is remunerative.

3.The scheme envisages supply of electricity to Kasargode, Kudlu and Mogralu villages. The load forecasts in the 1 st. and 10th year is as follows:

Load Forecast.	1st Year.	10th Year.
Industrial	760 H.P.	760 H.P.
Agricultural	76 H.P.	275 H.P.
Domestic	645 Nos.	880 Nos.
Streetlights	270 Nos.	270 Nos.
F.R.S.C.(Shops)	120 Nos.	210 Nos.
Cinemas	2	2

The types of industrial loads expected are mainly Saw Mills, Oil Mills (and flour mills. There are no rice mills) included in the scheme. The agricultural loads contemplated are mainly for pumping water for agricultural purposes from wells and rivers having copious supply of water in the area.

4.Out of the three villages included in the scheme, Mogralu is under the National Extension Service Scheme of Kumbla firka in Manjeswar Block of South Kanara District. The main/K.V. feeder provided in the scheme will enable individual small extensions to be made to other villages also if the

scheme is completed. The source of the supply will be from Jog Hydro-electric Scheme and the initial scheme is expected to be completed in one year after the scheme is sanctioned by the Government by which time the Jog Supply to South Kanara District would have materialised.

5.Kasargode town, which has been included in the scheme, is already having electricity on a small scale, generated and distributed by a licensee M/S. Kanara Ceremic's Ltd. and the licensee is not able to meet the growing demand even within the town areas. It is therefore proposed to take over the undertaking by the Government so that supply position may be improved and the growing demand of the public in the town fully met. A provision of Rs.75,000/- towards compensation to the licensee in the first year has been provided in the estimate.

6.In view of the States Re-organisation proposals, provision has not been included in the Part II Scheme proposals for 1956-57 for the acquisition of the Kasargode undertaking. Therefore it has to be considered whether the present proposal which includes acquisition of the above undertaking may be proceeded with. It may however be mentioned that there has been great agitation in South Kanara District about the postponement of the acquisition of the Mangalore Undertaking and allegations were also made that the Government have dropped extension schemes in the district in view of the S.R.C.Report. The allegations are no doubt baseless.

7.The estimated cost of the scheme exceeds Rs. 2 lakhs. The scheme has therefore to be treated as new service and placed before the S.F.C. and the Cabinet. The approval of Legislature has also to be obtained in due course. To sanction the scheme following the above procedure will take some time and by that

45 2/56
555/13 /R

time the final decision regarding the States Re-organisation proposals is likely to be known. The Chief Engineer had also reported separately that the acquisition of the undertaking is programmed only for March 1957. If Kasargode is to go to another State, the acquisition will have to be done only by that State. In the circumstances, this department proposed that the scheme may be sanctioned after obtaining the approval of the S.F.C. and the Cabinet. Finance department have agreed.

8. The file may be circulated to Minister (Works) and Minister (P & E) for orders whether the scheme for extension of supply of power from Kumbla to Kasargode and en-route villages in South Kanara District may be placed before the S.F.C. for consideration.

1167 This I

16/3/56 SR 16/3/56

17/3/56

R. M. Sundaram 15/3/56

S

Secretary (W)

for M (P & E)

C. Subramaniam 21.4.56.

Please see the orders in Circulation above. A draft note for the S.F.C. is sorted for approval. Fin may see for acceptance.

ASSISTANT SECRETARY TO GOVERNMENT 16 28/4/56

31/5/56 SR 31/5/56

18/5/56

Pwd no 452/56-2 4/5/56

Fin (EB) Dept

The draft note for the S.F.C may be accepted.

15/5/56

PW.

Fin U.O.No. 4547 EB 15-5-56

(33)

(Cno.455E/56.) Pwd(E2)

The draft note for the S.F.C. bellas, which has been accepted by Finance + bottom of pb ante may now be issued.

Sh
17/5/56
SR
17/5/56

L
17/5/56

Y
9/5/56
S

The note for the S.F.C. has been issued. Six copies of the note have been placed below. The file may be sent to Finance.

Sh
4/6/56
SR
4/6/56

L
4/6/56

Fin

Pwd No 455E/56-3
4/6/56

Finance (SFC) Department.

The Standing Finance Committee approved the proposal.

25-9-56 25.9.56

5988

Pwd(E2)

Fin UO No. 51971 S.F.C-1 d.s
25-9-56

The Standing Finance Committee approved the proposal dealt with in this file. According to the Finance Department's U.O. note no. 77134 SFC (7) dt. 26-9-56, the Scheme need not be placed before the Cabinet. A draft order is

ASSISTANT SECRETARY TO GOVERNMENT
5 - JUN 1956
FINANCE DEPARTMENT
51971

ASSISTANT SECRETARY TO GOVERNMENT
5827
26 SEP 1956
PUBLIC WORKS DEPARTMENT

(Cro 4582/56)

Submitted for approval. Two days may be before issue [with reference to R on page 6 ante, it is submitted that according to the S.R.C. Act, Southern Kanara Coorg Kasaragode taluk of to Kerala State & the remaining taluks to Mysore State]

Ur 4.10.56. Sue 5.10.56

It would appear that a large portion of the area to be benefitted by this scheme would go to Mysore State while Kasaragode will go to Kerala State. It is for consideration whether this scheme which is for the benefit of areas which will form part of two different States needs be sanctioned now. Perhaps we may sanction the scheme and leave it to Mysore to revise the scheme later by excluding the areas going to Kerala.

I think this is the only course to take Ur 12.10.56 A

Pub (Partn.) and Fin may see for remarks

15/10/56

Ur 12.10.56

[Change to Blue] Ur 12.10.56

Pub (Partn) | Fin
Pub. (Partn) Dept.

Pwsno 4582/56-4
15/10/56

The note of P.W.D from p 4 above and the draft order below may be perused. The proposal at A above may be agreed to in this Dept. The case may be passed on to Fin.

Ed 16/10/56. CS 17/10/56

17/X/56

Finance

Pub. (part)-ro. no 4780/56-1
17/10/56

DEPUTY SECRETARY TO GOVERNMENT 92884 18 OCT '56

CONSTANT SECRETARY to G 4780 16 OCT 1956 PUBLIC CONSTRUCTIONS

Cm. 455/56 — Fin (Exp)

(Pre fin note on p7 above)

This dept may agree with the view at A on p8 above. The draft order below may be accepted.

18.10.56 — 18/10/56 — Dy S. Fin.

This dept 18/10/56

Apparently, no expdr will be incurred on this scheme by this Govt, as the area served moved to other States from 1.11.56. In that case, the question of getting the approval of the Madras Legislature and of this Govt's sanctioning an advance from the Contingency Fund will not arise. Para 2 of the draft may be amended as indicated. The file may be transferred to the Purpose Govt for further action, after issue of the order.

19/10/56 — 19/10/56

Fin no 92984-Bg1/19.X.56:

632 21E/56 — 23/10/56 — Pur (Sp)

A.S.

Please see the views of Public (Partition) at p8-9 and Fin dept p1 above. The draft order below as amended by Fin dept may now be issued.

23/10/56

23.10.56

23/10/56.